

Pricing Line Item	Pricing Line Item	Pricing Line Item	Pricing Line Item	Pricing Line Item	Pricing Line Item
Order	Type	Description	Unit Of Measure	Quantity	Unit Price Estimate
1	Base	Mobilization / Demobilization	LS	1	
2	Base	E&S controls - provide, install, and maintain erosion and sediment controls (120' 12" Compost Filter Sox, 2 inlet protection, 1 concrete wash out	LS	1	
3	Base	Provide, install, and maintain temporary 6' height chainlink security fencing to secure site; to include removal at end of project	LF	961	
4	Base	Protective Fencing - provide, install, and maintain 48" high, 20 mil orange construction fencing and posts around existing trees and shrubs to remain; remove at time of substantial completion; to include removal at end of project	LF	548	
5	Base	Tree Removal - 6 existing mature trees around central circle including stumps and roots over 3" diameter in size to a minimum depth of 12" below grade; haul debris off site and dispose of accordingly	EA	6	
6	Base	Hedge Removal - Remove designated existing hedge shrubs including roots over 3" diameter. Haul debris off site and dispose of accordingly	LS	1	
7	Base	Sign Removal - remove designated existing signs, haul material off site and dispose of accordingly	EA	3	
8	Base	Decorative Light Removal - Remove nine designated existing light poles and bases; deliver decorative poles and fixtures to Centre Park Historic District Artifacts Bank (3 blocks from site)	EA	9	
9		Light Removal - Remove designated existing shoe-box style fixtures and bases, haul debris off site and dispose of accordingly	EA	3	
10	Base	Asphalt Pavement Removal - sawcut and remove full depth of existing asphalt pavement and stone subbase; haul material off site and dispose of accordingly	SY	407	
11	Base	Concrete Pavement Removal - sawcut and remove full depth of existing concrete pavement and stone subbase; haul material off site and dispose of accordingly	SY	5	
12	Base	Brick / Concrete Pad Removal - remove full depth of existing brick / concrete pad and stone subbase; haul material off site and dispose of accordingly	SY	5	
13	Base	Existing Fountain Pavers Removal - remove brick pavers and stone subbase within fountain area; haul material off site and dispose of accordingly	SY	74	
14	Base	Remove and store ,on site, 13 existing fountain stone boulders on site for re-installation in landscape beds	LS	1	
15	Base	Fountain Vault Removal - Remove concrete fountain vault and associated piping; haul material off site and dispose of accordingly	LS	1	
16	Alternate	Pavement Milling - Provide all required certified and insured professional labor and equipment to mill and retain 1" of asphalt material; haul material off site and dispose of accordingly	SY	47	
17	Base	Supply and install 4" integral color class AA concrete walkway around fountain with stone subbase	SY	219	
18	Alternate	Supply and install min. 1.5"thick bluestone pavers in random rectangular pattern on 4" concrete with 6x6 WWM base on stone subbase	SY	219	
19	Base	Supply and install 24"x12"x1.5" bluestone paver bands on 4" concrete with 6x6 WWM base on stone subbase	SY	13	
20	Base	Supply and install 8" 4500 psi concrete fountain basin with #4 rebar reinforcement on stone subbase, contractor responsible for concrete testing and reports	LS	1	
21	Base	Supply and install 4500 psi concrete basin floor walls and footings with #4 rebar reinforcement and cast stone wall coping secured with 1/2"x8" ss dowels on 1/2" mortar bed	LS	1	
22	Base	Supply and install 4500 psi concrete pedestal footing with #5 rebar reinforcement	LS	1	

23	Base	Three-tiered fountain and utilities- Provide all required certified and insured professional labor and equipment to supply and install new Robinson Iron "Caesar" fountain in Robinson Verde Gris color, fountain control panel mounted on back of new information kiosk, 4'x4' vault with vents, 1-1/2" vault drain line, vault french drain, 4" main drain line for fountain, and all associate fountain utilities shown on fountain plans	LS	1
24	Base	Powerwash, re-point , clean, and seal existing brick pavers and exterior face of seat wall in central circle area with Glen Gery G-209 colored mortar	SY	152
25	Base	Supply and install 1" HDPE SDR 9 pipe and clean stone backfill	LF	801
26	Base	Supply and install 4" HDPE pipe and clean stone backfill; tie into existing storm inlet on N. 4th St.	LF	252
27	Base	Supply and install 4" perforated pvc pipe and clean stone backfill and slotted end caps	LF	79
28	Base	Supply and install water ground hydrants	EA	6
29	Base	Supply and install Tyler Series 6860 Valve Boxes with associated bases	EA	3
30	Base	Lighting - Provide all required certified and insured professional labor and equipment to supply and install 12' ht. HADCO P1516 light poles on 3500 psi concrete base and HADCO New London fixtures	EA	16
31	Base	Supply and install Legrand Wiremold Outdoor Ground Boxes	EA	3
32	Base	Supply and install Sch. 40 conduit and underground electrical wiring,	LF	725
33	Base	Supply and install dry-laid stone wall on stone subbase with stone backfill, class 4 non-woven geotextile fabric, and 4" perforated pvc pipe to daylight	LF	85
34	Base	Supply and install 4" class A concrete pad for trash receptacle	SY	1
35	Base	Supply and install trash receptacle (added in Addendum 1)	EA	1
36	Base	Supply and install brick pavers on 1" mortar bed with mortared joints on 6" class A concrete base with stone subbase for bench pads	SY	12
37	Base	Supply and install 8' Keystone Ridge Designs Lamplighter Bench (L28C), color - Evergreen on brick/concrete pad	EA	5
38	Base	Supply and install full-depth concrete sidewalk restoration at corner of N. 4th and Douglas Streets	SY	5
39	Base	Supply and install 1-1/2" Superpave Asphalt Mixture Design wearing course, PG 64S-22, 0.0 to 0.3 millions esals, 9.5 mm mix, SRL-L	SY	186
40	Base	Supply and install 3" Superpave Asphalt Mixture Design base course, PG 64S-22, 0.0 to 0.3 millions esals, 19.0 mm mix,	SY	186
41	Base	Supply materials and equipment to clean and fill crack in existing bituminous walk and sealcoat walks	LS	1
42	Alternate	Supply and install 1" Superpave Asphalt Mixture Design wearing course, PG 64S-22, 0.0 to 0.3 millions esals, 9.5 mm mix, SRL-L	SY	433
43	Base	Supply and install 4' three rail picket wrought-iron fence; finish - black powdercoat; posts set in 3500 psi concrete	LF	93
44	Base	Supply and install 4' three rail picket wrought-iron fence gate with lockable latch; finish - black powdercoat	EA	1
45	Base	Supply and install Park Rules and Pet Clean-Up Signs on 2" sq. aluminum posts set in 3000 psi concrete	EA	4
46	Base	Supply and install Information Kiosk on (2) 4" sq. aluminum posts set in 3000 psi concrete	LS	1
47	Base	Supply and install Park History Sign on (2) 4" sq. aluminum posts set in 3000 psi concrete	LS	1
48	Base	Supply and install 'No Wading in Fountain' signs on 1" aluminum bars around fountain	EA	6
49	Base	Supply and install 6" amended topsoil in designated landscaped areas	CY	40
50	Base	Restore granite belgian block landscape edging on mortar bed on class AA concrete base; to include expansion 1/2" wide expansion joints filled with preformed bituminous-impregnated fiber	LF	10
51	Alternate	Supply and install granite belgian block landscape edging on mortar bed on class AA concrete base; to include expansion 1/2" wide expansion joints filled with preformed bituminous-impregnated fiber	LF	121
52	Base	Supply and install Picea pungens 'Baby Blue Eyes' Baby Blue Eyes Colorado Blue Spruce; B&B; 8' ht. min; single leader	EA	1

53	Base	Supply and install Cornus kousa 'Satomi' Satomi Kousa Dogwood; B&B; 10' ht. min; specimen, single leader	EA	3
54	Base	Supply and install Ulmus americana 'Valley Forge' Valley Forge American Elm; B&B; 3" cal. min; specimen, single	EA	4
55	Base	Supply and install Nyssa sylvatica Black Gum; B&B; 3" cal. min; specimen, single leader	EA	3
56	Base	Supply and install Cercis canadensis Eastern Redbud; B&B; 2" cal. min; specimen, single leader	EA	3
57	Base	Supply and install Prunus serrulata Japanese Flowering Cherry; B&B; 2" cal. min; specimen, single leader	EA	1
58	Base	Supply and install Magnolia x soulangeana Saucer Magnolia; B&B; 2" cal. min; specimen, min. three-equal stems	EA	1
59	Base	Supply and install Ilex glabra 'Gem Box' Gem Box Inkberry; container; 18" ht. min; matched	EA	3
60	Base	Supply and install Rhododendron 'P. J. M. Elite'; container; 36" ht. min; matched	EA	9
61	Base	Supply and install Ilex x meserveae 'Castle Sprite' Castle Sprite Blue Holly; container; 36" ht. min; matched	EA	2
62	Base	Supply and install Buxus sempervirens 'Suffruticosa' Dwarf English Boxwood; container; 12" ht. min; matched	EA	128
63	Base	Supply and install Azalea x 'Hino Crimson'; container; 12" ht. min; matched	EA	3
64	Base	Supply and install Azalea x 'Karen'; container; 12" ht. min; matched	EA	3
65	Base	Supply and install Hydrangea macrophylla 'Mini Penny'; container; 18" ht. min; matched	EA	18
66	Base	Supply and install Hydrangea paniculata 'Fire Light Tidbit'; container; 18" ht. min; matched	EA	3
67	Base	Supply and install Rosa x 'Sweet Drift' Sweet Drift Rose; container; 12" ht. min; matched	EA	18
68	Base	Supply and install Rosa x 'White Drift' White Drift Rose; container; 12" ht. min; matched	EA	20
69	Base	Supply and install Liriope muscari 'Big Blue' Big Blue Lilyturf; #1 container; 12" ht.	EA	448
70	Base	Supply and install Osmundastrum cinnamomeum Cinnamon Fern; #1 container; 24" ht.	EA	48
71	Base	Supply and install Iris pallida 'Variegata' Variegated Sweet Iris; #1 container; 12" ht.	EA	43
72	Base	Supply and install Lilium lancifolium Orange Tiger Lily; #1 container; 12" ht.	EA	33
73	Base	Supply and install Aquilegia canadensis Columbine; #1 container; 12" ht.	EA	5
74	Base	Supply and install Rudbeckia fulgida var. sullivanti 'Goldstrum' Goldstrum Black Eyed Susan; #3 container; 12" ht.	EA	12
75	Base	Supply and install Stachys byzantine Lambs Ear; #1 container; 12" ht.	EA	54
76	Base	Supply and install Heuchera x 'Mahogany Monster' Mahogany Monster Coral Bells; #1 container; 12" ht.	EA	29
77	Base	Supply and install Heuchera x 'Peachberry Ice" Peachberry Ice Coral Bells; #1 container; 8" ht.	EA	16
78	Base	Supply and install Heuchera x 'Appletini" Appletini Coral Bells; #1 container; 8" ht.	EA	14
79	Base	Supply and install Hosta x 'August Moon'; #3 container; 12" ht.	EA	19
80	Base	Supply and install Hosta x 'Korean Snow'; #3 container; 12" ht.	EA	6
81	Base	Supply and install Hosta x 'Blue Hawaii'; #3 container; 12" ht.	EA	18
82	Base	Supply and install Narcissus x 'Akita' Akita Trumpet Daffodil; bulb; large; #1 quality	EA	225
83	Base	Supply and install Narcissus x 'Dutch Master' Dutch Master Trumpet Daffodil; bulb; large; #1 quality	EA	225
84	Base	Remove E&S controls after 85% vegetative cover establishment approved by the Landscape Architect. Spread compost, remove wood chips, install permanent seed and straw mulch disturbed areas.	LS	1