



PROPOSAL AND CONTRACT (WHEN EXECUTED)

INSTRUCTIONS ON PAGE 4

THIS PROPOSAL INCLUDES INSTRUCTIONS TO BIDDERS

A. DEPOSIT OF PROPOSALS.

All envelopes containing Bid proposals shall be clearly marked "Bid Proposal for letting of December 4, 2015 ." DATE

City of Reading MUNICIPALITY (NAME & TYPE)

Linda A. Kelleher CITY CLERK

Sealed Proposals will be received on or before 2:00 PM on the above Letting Date. TIME

815 Washington Street Reading, PA 19601 ADDRESS

Bids will be opened and read at approximately 2:00 PM , on the above Letting Date. TIME

PROPOSALS MUST BE MAILED OR OTHERWISE DELIVERED TO THE ABOVE ADDRESS.

- 1 The contractor proposes to furnish and deliver all materials (including Form CS-4171, CERTIFICATE OF COMPLIANCE and/ or TR-465 DAILY BITUMINOUS MIXTURE CERTIFICATION) and to do and perform all work on the following project as more specifically set forth in the Schedule of Prices (Attachment), in accordance with drawings and specifications on file at City of Reading Web Site as well as the supplements and special requirements contained herein and/ or attached hereto and current PennDOT Specifications (Publication 408), except (a) bidders must be prequalified by Penn DOT, however subcontractor need not be prequalified by PennDOT (Sec.102.01), and (b) Volumetric testing of bituminous paving materials is not required (Sec. 409).
2 If designated as the successful bidder, the contractor will begin work on the date specified in the notice to proceed, or as otherwise provided in the special requirements, and will complete all work by Friday, July 01, 2016
3 Accompanying this proposal is a certified check or bid bond in the amount of 10% made payable to the municipality as a proposal guarantee which, it is understood, will be forfeited in case the contractor fails to comply with the requirements of the proposal.

B. PROPOSAL OF:

NAME / ADDRESS OF CONTRACTOR

CONTRACTORS CERTIFICATION

It is hereby certified as follows:

- 1 The only person interested in the proposal as principal (s) is (are):
2 None of the above persons are employees of the municipality.
3 This proposal is made without collusion with any other person, firm or corporation.
4 All plans and specifications referred to above and the site of the work have been examined by the contractor. The contractor understands that the quantities indicated herein are approximate and are subject to change as may be required; and that all work is payable on the basis of the unit price listed on the Schedule of Prices. (Attachment 1).

- 5 The contractor will comply with all requirements of the laws and implementing regulations of the Commonwealth of Pennsylvania and the United States relating to human relations, equal opportunity and non-discrimination in employment, and will pay to workmen employed in the performance of the contract the wages to which they may be entitled.

- 6 The contractor will provide the municipality with a performance bond, conditioned upon the faithful performance of the contract in accordance with the plans, specifications and conditions thereof, and a payment bond, conditioned on the prompt payment of all material furnished and labor supplied or performed in the prosecution of the work, in accordance with the Public Works Contractors' Bond Law of 1967; and an affidavit accepting the provisions of the Workmen's Compensation Act of 1915, as amended.

CONTRACTOR

BY: _____ DATE: _____
TITLE:

WITNESSED OR ATTESTED BY: _____ DATE: _____
TITLE:

TO BE EXECUTED ONLY IN THE EVENT THE ABOVE PROPOSAL IS ACCEPTED


ACCEPTED ON : _____
DATE

MUNICIPALITY

BY: _____
TITLE:

BY: _____
TITLE:

BY: _____
TITLE:



ATTESTED BY: _____
TITLE:



**ATTACHMENT 1
TO MS - 944 (PROPOSAL AND CONTRACT MS - 944)**

County: Berks Municipality: City of Reading
Project Number: 2015 Repaving Project

LOCATION OF WORK:

1. North 6th Street between Spring Street and Amity Street
2. South 9th Street between Laurel Street and Bingaman Street
3. Hill Road between Clymer Street and the City line at Egelman's Park.

DESCRIPTION OF WORK:

1. Demolish existing curb ramps, sidewalks and alley entrances and install new ADA compliant curb ramps, sidewalks and alley entrances
2. Street surface preparation including pavement milling, paving notches, select base repair and adjusting manhole frames and other utility boxes to match final grades. Place leveling and wearing courses and apply pavement markings and install traffic control signage.
3. Contractor shall coordinate with utility providers and shall reset manhole lids, boxes, valves, etc. as needed to avoid interference with the Work.
4. Traffic control and brief street closures as needed.
5. Apply asphalt leveling and overlay courses within the limits of work.

ESCALATOR CLAUSE:

This contract contains sufficient quantities of asphalt cement for the PennDOT bituminous price adjustment to apply. PennDOT Pub. 408, Section 110.04 will apply to quantities of bituminous materials greater than 100 tons of asphalt cement including asphalt cement residue contained in emulsions or cutbacks. (See Attachment 1-A for more information)

THIS PORTION TO BE COMPLETED BY THE MUNICIPALITY

SCHEDULE OF PRICES

1 Item No.	2 Approximate Quantities	3 Unit	4 *Description	5 Unit Price	6 Total
A. Base Bid: N. 6th Street from Spring St. the Amity St. and S. 9th Street from Laurel St. to Binaman St.					
0203-0004	37	CY	Class B Excavation, Select Base Removal		
0309-0424	56	SY	SUPERPAVE ASPHALT MIXTURE DESIGN, HMA BASE COURSE REPAIR, PG 64-22, 0.3 TO < 3 MILLION ESALs, 25.0 MM MIX, 5" DEPTH		
0409-1592	518	TON	Superpave Asphalt Mix Design, HMA Wearing, Leveling Course, PG 64-22, 0.3 to 3 M ESAL's, 9.5 MM Mix, 75 LB/SY		
0409-0482	1,396	TON	Superpave Asphalt Mix Design, HMA Wearing Course, PG 64-22, 0.3 to 3 M ESAL's, 9.5 MM Mix, 1-1/2" Depth, SLR-H		
0491-0012	16,773	SY	Milling of Bituminous Pavement Surface, 1 1/2" Depth, Milled Material Retained by Contractor		
0606-0150	10	Set	Grade Adjustment of Manholes		
0695-0003	282	SF	Detectable Warning Surface - Composite Concrete		
0901-0001	1	LS	Maintenance and Protection of Traffic During Construction		
0964-0002	4,140	LF	4" Yellow Epoxy Pavement Markings		
0964-0005	1,768	LF	6" White Epoxy Pavement Markings		
0964-0021	210	LF	24" White Epoxy Pavement Markings		
9000-0001	16	Each	ADA Curb Ramp, Type 1, Single, Design/Build		
9000-0002	16	Each	ADA Curb Ramp, Type 1, Double, Design/Build		
9000-0003	3,537	SF	Plain Cement Concrete, Sidewalk		
9000-0004	360	SF	Plain Cement Concrete, Alley Entrance		
			Subtotal of A. Base Bid		
			Continued on ATTACHMENT No. 1.2		

ATTACHMENT NO. 1.2

1 Item No.	2 Approximate Quantities	3 Unit	4 *Description	5 Unit Price	6 Total
B. Add Items: Hill Road from Klymer St. to the City Line at Egleman's Reservoir					
0203-0004	19	CY	Class B Excavation, Select Base Removal		
0309-0424	56	SY	SUPERPAVE ASPHALT MIXTURE DESIGN, HMA BASE COURSE REPAIR, PG 64-22, 0.3 TO < 3 MILLION ESALs, 25.0 MM MIX, 5" DEPTH		
0409-1592	557	TON	Superpave Asphalt Mix Design, HMA Wearing, Leveling Course, PG 64-22, 0.3 to 3 M ESAL's, 9.5 MM Mix, 75 LB/SY		
0409-0482	1,506	TON	Superpave Asphalt Mix Design, HMA Wearing Course, PG 64-22, 0.3 to 3 M ESAL's, 9.5 MM Mix, 1-1/2" Depth, SLR-H		
0491-0012	18,088	SY	Milling of Bituminous Pavement Surface, 1 1/2" Depth, Milled Material Retained by Contractor		
0606-0150	6	Set	Grade Adjustment of Manholes		
0901-0001	1	LS	Maintenance and Protection of Traffic During Construction		
0964-0002	5,814	LF	4" Yellow Epoxy Pavement Markings		
0964-0021	18	LF	24" White Epoxy Pavement Markings		
			Subtotal of B. Add Items		

*** DESCRIPTION:**

Must include ADT on wearing surfaces
**USE OF CUTBACK ASPHALT IS PROHIBITED
 BETWEEN MAY 1st AND OCTOBER 31st, EXCEPT
 AS NOTED IN BULLETIN NO. 25.
 FOR OPTION OR PHASE BIDS THE TOTALS FOR
 EACH MUST BE INCLUDED.**

	SUBTOTAL A. + B.
SUBTOTAL FROM OTHER ATTACHMENTS	
BID TOTAL FOR A NON OPTION / PHASE BID	
OPTION 1 OR PHASE 1 BID TOTAL	
OPTION 2 OR PHASE 2 BID TOTAL	
OPTION 3 OR PHASE 3 BID TOTAL	

